KHARAGPUR COLLEGE KHARAGPUR DIST.- PASCHIM MEDINIPUR

Tender Notice No.-

Dated- 13.09.2024

Notice Inviting Quotation for Labour Rate for Painting Work In Class

Room Building of Kharagpur College

Office of the Principal, Kharagpur College, invites sealed tenders in the enclosed format for Labour Rate for Painting work in Class Room Building of the college as per details given below. Sealed tenders must be dropped in the Tender Box in the Office of the Principal, Kharagpur College, Kharagpur-721305 on or before 21.09.2024. Interested Tenderer may visit the site and contact the office before dropping tenders.

Payment will be made after satisfactory work.

Sd/-Principal

Labour Rate for Painting Work In Class Room Building of Kharagpur College

Name of the Contractor : Address & Mobile No. PAN No.

| SL. No. | Description of Items | Units | Quantity | | Total Amount |
|---------|---|-----------|-----------|--------|--------------|
| | | | | Rs. P. | Rs. P. |
| 01 | Labour for Scraping of moss, blister etc. | | | | |
| | thoroughly from exterior surface of wall | | | | |
| 1 | necessitating the use of scraper, wire | | | | |
| 1 | brush etc.(payment againest this item | | | | |
| 1 | will be made only when this has been | | | | |
| 1 | done on the specific direction of the | | 2000 | | |
| | engineer-in-charge | Sq. m. | (approx.) | | |
| | | 111. | | | |
| | | | | | |
| 1 | Labour for Removing old scales, blister | | | | |
| 1 | etc. of interior surface of walls , ceiling | | | | |
| 1 | by scraping etc. and preparing smooth | | | | |
| 1 | and even surface with rendering or | | | | |
| | cement mortar (1:2)(as necessary), to | | | | |
| 1 | make the surface suitable for receiving | | | | |
| 1 | distemper. (payment against this item | | | | |
| 1 | will be made only when this has been | | 2000 | | |
| 1 | done on the specific direction of the | | 2000 | | |
| | engineer-in-charge). | Sq. m. | (approx.) | | |

| 03 | Labour for Acrylic distemper to interior wall, ceilling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothening of surface. Two Coat | | 2000 (approx.) | |
|----|---|-----------|-------------------|--|
| | | | | |
| 04 | Labour for Bordering (upto 75mm. Width) in distemper excluding cost of materials by two coats acrylic distemper and one coat solvent based acrylic primer. | | 100 (approx.) | |
| 05 | Labour for Bordering (upto 75mm. Width) in distemper excluding cost of materials by two coats synthetic distemper and one coat solvent based acrylic primer. | | 100 (approx.) | |
| 06 | Applying exterior grade 100% acrylic of approved quality and brand on plastered or concrete surface old or new surface to received decorative textured (matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacture's specification and as per direction of the EIC. (a) One coat | | 1000 (approx.) | |
| 07 | Labour for Removing loose scales, blisters etc. froom old painted surface and thoroughly smoothening the surface to make the same suitable for receiving fresh coat of paint. | | 1000 (approx.) | |
| 08 | (a) Labour for Cleaning the wall and ceiling by scraping, sand papering and smoothening down the surface including putting. | Sq. m. | 2000 (approx.) | |
| | (b) Labour for Washing & cleaning the wall surface & ceiling by soft detergent powder & soft water & render the surface free of dust, stain etc. | | 2000 (approx.) | |

| | | m. | | | |
|----|--|-----------|---------------|-----------|--|
| | | | | | |
| | | | | | |
| | | | | | |
| 09 | (a) Labour for Priming one coat on | | | | |
| | timber or plastered surface with | | | | |
| | synthetic oil bound primer of approved | | | | |
| | quality including smoothening surfaces | Sq. | 50 (aprox.) | | |
| | by sand papering etc. | m. | \ \ \ \ \ \ \ | | |
| | (b) Priming one coat on steel or other | | | | |
| | metal surface with synthetic oil bound | | | | |
| | primer of approved quality including | | 50 | | |
| | smoothening surfaces by sand | | (approx.) | | |
| | papering etc. | m. | | | |
| 10 | Labour for Painting with best quality | | | | |
| | synthetic enamel paint of approved | | | | |
| | make and brand including smoothening | | | | |
| | surface by sand papering etc. including | | | | |
| | using of approved putty etc. on the | | | | |
| | surface, if necessary: (a)On timber or | 0 | 50 | | |
| | plastered surface: | Sq. m. | (approx.) | | |
| | a. With super gloss (hi-gloss)- (i) One coat | | | | |
| | (ii)Two coat | | | | |
| - | b. With other than hi-gloss of approved | | | | |
| | quality- | | | | |
| | (i) One coat | | | | |
| | (ii)Two coat | | | | |
| 11 | Labour for fixing best indian sheet glass | | | | |
| | panes set in putty and fitted and fixed | | | | |
| | with nails and putty complete. (In all | | 50 | | |
| | floor for internal wall & upto 6 m hight | • | (approx.) | | |
| | for external wall) (i) 3 mm to 6 mm thick | m. | | | |
| 12 | Labour for White washing including | | | | |
| '^ | cleaning and smoothening surface | | | | |
| | thoroughly. All floor | Ca. | | | |
| | | Sq. m. | | | |
| | (a) One coats. | | | | |
| | (b) Two coats(to be done on specific | | | | |
| | instruction). | | | | |
| | | | | Total Rs. | |
| | | | | | |
| | | | • | | |

Employer's (College Authority) responsibility:

Supply of required amount of paints,

*Paint specification would be determined by College Authority / Consultant

*Power and Water supply.

Contractor's (Tenderer) responsibility:

- *To bring all the necessary ancillary items such as Paintbrush, power brush, wire brush, cup brush, scaffolding material, rope, sand blasting equipment, water pump, Emery cloth of different grade and all other tools;
- *Sand and coal powder etc. for sand blasting;
- *Surface preparation and painting as per direction, instruction and guidelines given by College Authority / Consultant
- *Arrange PPE for the personnel;
- *In case of personal injury, defect of contractors tool and apparatus repair/remedy shall be done by contractor;
- *Maintaining proper safety procedure at job site,
- *Food, accommodation and mobilization/demobilization to project site of personnel;
- *Painting and sand blasting job is required to be completed within four weeks' of issuing of work order.
- *You are requested to visit the job site with intimation at your own expense prior to submitting the quotation.

Signature of the officer, Opening the tender Date: Signature of the contractor Date: